

# TAXIWAYS RECONSTRUCTION PROJECT, Year 1 – Taxiways D, E, F, Q

## FACT SHEET

In February 2025, work will commence on a \$15.4 million, 6-month project to reconstruct segments of Taxiways D, E, F, and Q. This project will deliver important upgrades and extended lifespan to the airfield facilities that contribute to VNY’s world-class status. Improvements will be phased to maximize federal grant reimbursements and minimize operational impacts during construction.

Work will include reconstruction of:

- Taxiways D, E, and F from Runway 16R-34L to 16L-34R
- Taxiways E and F between Taxiway A and Runway 16R-34L
- Taxiway Q between Taxiway B and Runway 16R-34L

This project will be managed by Los Angeles World Airports’ Development Group with RS&H, Inc. as the engineer of record and Griffith Company as the general contractor.

Reconstruction includes:

- Full-depth asphalt pavement section reconstruction
- Infield grading and drainage improvements
- Airfield electrical improvements
- Airfield lighting and signage
- Pavement markings

### Operational Impacts

The construction was strategically phased to minimize operational impacts. The anticipated construction schedule and primary operational impacts are:

Tasks / Operational Impacts	Date(s)	Duration
<b>Mobilization NTP</b>	November 4, 2024	~3 months
<b>Construction</b>		
<b>Runway 16L-34R closed</b>	Construction Phase 1 thru 3A ~mid-February 2025 to mid-May 2025	~3 months
<b>Runway 16R-34L Shortened at TXY E</b> <ul style="list-style-type: none"><li>• ILS offline</li><li>• Reduced declared distances</li></ul>	Construction Phase 1 thru 2A ~mid-February 2025 to mid-April 2025	~2 months
<b>Runway 16R-34L Shortened at TXY F</b> <ul style="list-style-type: none"><li>• ILS offline</li><li>• PAPI replaced by temporary PLASI</li><li>• Reduced declared distances</li><li>• 16R threshold displaced</li></ul>	Construction Phase 2 thru 3B ~mid-April 2025 to late-June 2025	~2.5 months
<b>Runway 16R-34L nightly closure with daily reopening</b>	Construction Phase 4A thru 4 ~late-June 2025 to early-August 2025	~1 month

### Target Construction Schedule

Phase	Description	Duration (Calander)	Anticipated Start
1A	Phase 1 Pre work - RWY 16L-34R Shortening	4 Nights	February 2, 2025
1	TWY D Reconstruction	52 Days	February 11
2A	Phase 2 Pre-work - RWY 16R Threshold Displacement	4 Nights	April 13
2	TWY E (east) and F (east) Reconstruction	31 Days	April 17
3A	Phase 3 Pre-work	2 Nights	May 18
3	TWY E (west) and F (west) Reconstruction	33 Days	May 20
3B	Phase 3 Post-work - RWY 16R Threshold Restoration	4 Nights	June 22
4A	Phase 4 Pre-Work - TWY Q (east) Investigation	7 Nights	June 26
4	TWY Q (east) Reconstruction	28 Nights	July 6

NOTE: Target construction dates and durations are subject to change.